BUILDING PRODUCT INFORMATION — BPIR:18NBGA-COM:2026.V2

180 N-Line galv fascia bracket

Component BPIR. Supersedes BPIR:18NBGA-COM:2023.v1. Issued under the Building (Building Product Information Requirements) Regulations 2022.

Product and manufacturer details

Product name	180 N-Line galv fascia bracket
Product identifier	18NBGA-COM
Manufacturer's name & address	Refer to Table 2 for Continuous Group branded manufacturing locations and/or supply.
Manufacturer's NZBN	9429034817001 (Continuous Group Ltd). Regional NZBNs are listed in Table 2.
Manufacturer's email address	cg@continuous.co.nz
Manufacturer's web address	www.continuous.co.nz
Place of manufacture	Aotearoa New Zealand
Warnings & bans	No

Product description

180 N-Line fascia bracket is a component used in the installation of the 180 N-Line fascia system. It is a hidden component that provides a screw and nail free fascia face.

TABLE 1

COMPONENT	COMPONENT - MATERIAL
CG 180 N-Line Bracket	0.95mm G300 steel with minimum 125gsm alloy / zinc / magnesium protective coating

Installation requirements

Refer to 180 N-Line pre-painted metal fascia system BPIR:18NPM-SYS:2026.v2 for full system and installation details. Recommended maximum bracket spacing is 900mm, and within 200mm of corners.

Scope of use

180 N-Line galv fascia bracket is designed to fit 180 N-Line fascia.

Limitations of the use of this building product

1. Continuous Group fascia components should only be installed by a trade professional as part of the complete fascia system, and not to be undertaken as a DIY installation.

2. The bracket cannot be installed onto incompatible materials. The bracket cannot run off onto incompatible materials. Material compatibility, contact and run off to be adhered to in accordance with E2/AS1 Tables 20, 21 & 22. Stainless steel fixings and components are not compatible with Continuous Group materials.
3. The component forms part of the complete fascia system specified in the system BPIR and cannot be substituted under any circumstances.
4. Site locations must be evaluated in areas with high wind &/or salt &/or thermal/industrial atmospheric conditions. These types of locations may require specific engineering design (SED). Designers must consult metal supplier's information for specific durability requirements (reference E2/AS1 Table 20).

Maintenance requirements

Link to the Care and Maintenance Document below under "Supporting documentation".

1. The bracket is a hidden component and requires no direct maintenance. It is inspected as part of the fascia system — refer to the system BPIR and the Care and Maintenance Document.

Relevant building code clauses

COMPLIANCE / REGULATION	DETAIL
NZBC B1 Structure	Sections: B1.3.1, B1.3.2 & B1.3.3
NZBC B2 Durability	Section: B2.3.1 (b)
E2/AS1 External Moisture	Tables: 20, 21 & 22

180 N-Line galv fascia bracket contributes to compliance by —

NZBC B1 Structure sections B1.3.1, B1.3.2 & B1.3.3

The materials shown in Table 1 of this document meet the performance requirements of B1.3.1, B1.3.2 and B1.3.3.

NZBC B2 Durability section B2.3.1 (b) — durability of 15 years in compliance with NZBC B2

The bracket is moderately difficult to access or replace and any failure of the bracket would go undetected during normal use of the building but would be easily detected during normal maintenance.

E2/AS1 Table 20: "Material Selection"

The "CG 180 N-Line Bracket" is classified as "Hidden" (15 years) and material selection shown in Table 1 of this BPIR meets the requirements of Table 20 for exposure zones B, C & D: metallic-coated steel to AS 1397.

Warranty

The bracket carries the 15-year durability classification of the complete fascia system, provided the maintenance conditions are met. Refer to the system BPIR for full warranty terms.

Supporting documentation

The following additional documentation supports the above statements.

DOCUMENT NAME	WEBLINKS
180mm N-Line Fascia brochure & specification document	180 N-Line Fascia Brochure and Specifications 2021.pdf
180mm N-Line construction & drop height details	180 N-Line Fascia Construction and Drop Height Details Metal and Concrete Roofing 2021.pdf
Maintenance document	Continuous Group Maintenance Document.pdf
Material compatibility selection	Continuous Group Material Compatibility - Material Selection v1.pdf
Material compatibility in contact	Continuous Group Material Compatibility - Compatibility of materials in contact v1.pdf
Material compatibility subject to run off	Continuous Group Material Compatibility - Compatibility of materials subject to run off v1.pdf
Warranty document	Continuous Group Warranties

Manufacturing and supply locations

TABLE 2 — CONTINUOUS GROUP MANUFACTURING AND/OR SUPPLY LOCATIONS

LOCATION	COMPANY DETAILS
Northland	Northland Continuous Spouting Ltd (NZBN 9429032689105) 2 Sammaree Place, Kerikeri — northland@continuous.co.nz
Auckland	Continuous Spouting Auckland Ltd (NZBN 9429034029862) 94 Takanini School Road, Takanini, Auckland — auckland@continuous.co.nz
Waikato	Continuous Waikato and Bay of Plenty Ltd (NZBN 9429030330535) 141 Queens Street, Leamington, Cambridge — waikato@continuous.co.nz
Bay of Plenty	Continuous Waikato and Bay of Plenty Ltd (NZBN 9429030330535) 31B Enterprise Drive, Papamoa, Tauranga — bop@continuous.co.nz
Gisborne	Streetwise Spouting Ltd (NZBN 9429042306276) 4 Leith Street, Gisborne — gisborne@continuous.co.nz
Hawke's Bay	Rooftech Hawke's Bay Ltd (NZBN 9429035443889) 2/7 Cadbury Road, Onekawa, Napier — hawkes_bay@continuous.co.nz
Taranaki	Gutter Solutions Ltd (NZBN 9429036739240) Unit 2, 20 Pacific Place, Gonville, Whanganui — taranaki@continuous.co.nz
Whanganui / Manawatu	Gutter Solutions Ltd (NZBN 9429036739240) Unit 2, 20 Pacific Place, Gonville, Whanganui — manawatu@continuous.co.nz
Wellington	Wellington Continuous Spouting Ltd (NZBN 9429043333974) Unit B, 1 Prosser Street, Porirua — wellington@continuous.co.nz
Nelson / Marlborough	Continuous Spouting South Ltd (NZBN 9429050107209) 7 Fuji Court, Stoke, Nelson — nelson@continuous.co.nz
Westland	Continuous Spouting South Ltd (NZBN 9429050107209) 51-57 Revel Street, Hokitika — westland@continuous.co.nz
Christchurch / North Canterbury	Continuous Spouting South Ltd (NZBN 9429050107209) 16 Westland Place, Izone Industrial Estate, Rolleston — canterbury@continuous.co.nz
Mid / South Canterbury	Continuous Spouting South Ltd (NZBN 9429050107209) 126 Dobson Street, Ashburton — canterbury@continuous.co.nz
Central Otago	Continuous Spouting South Ltd (NZBN 9429050107209) 7 Connelly Way, Cromwell — otago@continuous.co.nz
Coastal Otago	Continuous Spouting South Ltd (NZBN 9429050107209) 8 Benson Close, Mosgiel — otago@continuous.co.nz
Southland	Continuous Spouting South Ltd (NZBN 9429050107209) 72 Leet Street, Invercargill — southland@continuous.co.nz

Continuous Group are members of the NZ Metal Roofing Manufacturers Incorporated and the Roofing Association of New Zealand.