BUILDING PRODUCT INFORMATION — BPIR:14NPM-SYS:2026.V2

140 N-Line pre-painted metal fascia system

System BPIR. Supersedes BPIR:14NPM-SYS:2023.v1. Issued under the Building (Building Product Information Requirements) Regulations 2022.

Product and manufacturer details

Product name	140 N-Line pre-painted metal fascia system
Product identifier	14NPM-SYS
Manufacturer's name & address	Refer to Table 3 for Continuous Group branded manufacturing locations and/or supply.
Manufacturer's NZBN	9429034817001 (Continuous Group Ltd). Regional NZBNs are listed in Table 3.
Manufacturer's email address	cg@continuous.co.nz
Manufacturer's web address	www.continuous.co.nz
Place of manufacture	Aotearoa New Zealand
Warnings & bans	No

Product description

140 N-Line Fascia is an architectural term for a frieze or band running horizontally or obliquely and situated vertically under a roof edge. The bracket system provides a screw or nail free face, eliminating filling and re-painting.

TABLE 1

SYSTEM COMPONENTS	COMPONENT - MATERIAL
140 N-Line Fascia Panel CG N-Line Soakers (as required)	Manufactured from "Factory Painted" pre-painted metal that complies with NZS:2728 (e.g. ColorCote or Colorsteel brands). Minimum 0.50mm BMT, grade G300 steel with minimum 200gsm zinc/alloy coating (Type 6).
CG 140 N-Line Bracket	0.95mm G300 steel with minimum 125gsm alloy / zinc / magnesium protective coating
Fastenings / fixings	Minimum Class 4 coated steel screws with a minimum 2.8mm depth head height and minimum 8 gauge screw thickness. Minimum 4/3 aluminium rivet fasteners. Fixings must be compatible with the substrate and bracket material. Stainless steel fixings and components are not compatible with Continuous Group materials.

Specifications & installation requirements

140 N-Line pre-painted metal fascia system is designed with the following system specifications when installed as per instructions.

TABLE 2

SYSTEM DETAILS	SPECIFICATION / INSTALLATION
Pre-installation design	Designers must review Construction Detail & Common Drop Heights before specifying this system, by utilising the online calculators available on the Continuous Group website.
Recommended maximum bracket spacing	900mm, and within 200mm of corners
Maximum soffit slope	30°
Corner styling	Soaker / hand cut mitre
Compatible spouting	Chief, Big Chief, Quartz, Quartz Plus, Cube 125, Halo 125, Halo 150, Archie-Box (limited to certain sizes)
Finish ranges	CG, Designer and Specialty ranges
Minimum fixings	Minimum Class 4 screw and/or rivet fasteners, compatible with the substrate and bracket material
Installation sequence	Install the bottom purlin after fascia installation.
Soffit bearers	Required on all hip corners. Gable ends may require packing under the rafter.

Scope of use

140 N-Line pre-painted metal fascia system is intended for use as fascia and barge board covering roof truss ends and gable ends around the roof perimeter of a building. It may be used to hold external gutters and soffit linings.

Limitations of the use of this building product

1. All Continuous Group fascia systems should only be installed by a trade professional and not to be undertaken as a DIY installation. Metal fascia is a specialised system — DIY installation is not recommended, supported or approved.
2. The system is designed to hold gutter and soffit systems only. The attachment of any form of "lean to" outdoor roof system or pergolas is prohibited.
3. The system cannot be installed onto incompatible materials. The system cannot run off onto incompatible materials. Material compatibility, contact and run off to be adhered to in accordance with E2/AS1 Tables 20, 21 & 22. Stainless steel fixings and components are not compatible with Continuous Group materials.
4. The system uses various components as specified in Table 1. These components make up the entire system and cannot be substituted under any circumstances.

5. The system cannot be used in exposure zone "E" (reference E2/AS1 Table 20). Pre-painted steel is suitable in zones B and C without conditions; zone D may require a pre-approval warranty application based on the site address.
6. Site locations must be evaluated in areas with high wind &/or salt &/or thermal/industrial atmospheric conditions. These types of locations may require specific engineering design (SED). Designers must consult metal supplier's information for specific durability requirements (reference E2/AS1 Table 20).

Maintenance requirements

Link to the Care and Maintenance Document below under "Supporting documentation".

1. Inspection of the system is required every 3 months to check for buildup of residue and organic matter on the face and underside of the fascia.
2. Wash the painted surface of the system at a minimum of every 6 months and immediately after inspection when required.

Relevant building code clauses

COMPLIANCE / REGULATION	DETAIL
NZBC B1 Structure	Sections: B1.3.1, B1.3.2 & B1.3.3
NZBC B2 Durability	Section: B2.3.1 (b)
NZBC F2	Section: F2.3.1
E2/AS1 External Moisture	Tables: 20, 21 & 22
NZBC C3 Fire Rating	Compliance
AS/NZS 4020:2018	Test of products for use in contact with drinking water
Code of Practice V23.09	Sections as noted in reference to further installation best practice

140 N-Line pre-painted metal fascia system contributes to compliance by —

NZBC B1 Structure sections B1.3.1, B1.3.2 & B1.3.3

The materials shown in Table 1 and the system details shown in Table 2 of this document meet the performance requirements of B1.3.1, B1.3.2 and B1.3.3.

NZBC B2 Durability section B2.3.1 (b) — durability of 15 years in compliance with NZBC B2

The system is moderately difficult to access or replace and any failure of the system would go undetected during normal use of the building but would be easily detected during normal maintenance.

NZBC F2 Hazardous Building Materials F2.3.1

The system, manufactured from pre-painted steel as shown in Table 1 of this document, will meet the performance requirements of F2.3.1.

E2/AS1 Table 20: "Material Selection" — fascia panel

The 140 N-Line Fascia Panel is classified as "Sheltered" and material selection shown in Table 1 of this BPIR meets the requirements of Table 20 for exposure zones B, C & D: "Factory painted" material to NZS 2728 (Type 6).

E2/AS1 Table 20: "Material Selection" — bracket

The "CG 140 N-Line Bracket" is classified as "Hidden" (15 years) and material selection shown in Table 1 of this BPIR meets the requirements of Table 20 for exposure zones B, C & D: metallic-coated steel to AS 1397.

E2/AS1 Table 21 & Table 22: "Compatibility of material in contact and subject to run-off"

All of the materials shown in Table 1 of this BPIR are compatible in contact and run-off with each other, provided they are installed and run off onto compatible materials.

NZBC C3 Fire affecting areas beyond the fire source

Colorcote and Colorsteel products are rated as Group 1-S when tested in accordance with ISO 5660:2002.

AS/NZS 4020:2018: "Testing of products for use in contact with drinking water"

Water that is in contact with material used in manufacturing Continuous Group fascia systems is safe for human consumption.

Warranty

A 15-year perforation warranty and 10-year paint warranty are provided in exposure zones B, C and D (ColorCote MagnaFlow and ColorSteel Maxam), provided the maintenance conditions are met. Zone D may require a pre-approval warranty application based on the site address.

NZMRM Code of Practice V23.09

This information is included to assist with further information outside of building code compliance.

8.3 & 8.3A Where the vertical planes of metal facings are exposed to sight, they should be designed to allow movement and minimise thermal buckling, and buckling from timber shrinkage. Maximum dimension between folds should be restricted to 300mm where possible, or swages installed to stiffen the panel. Constructing such flashings from thicker material will also help prevent distortion, but availability of such may be subject to minimum order quantities. Edges should be clip-fastened to allow thermal movement, and lengths over 6m should be installed with a thermal expansion joint. This can be constructed as an overlap, or a negative detail with sheet ends overlapping an under-soaker, with a gap between the ends of the exposed faces. Typically this gap would be 5mm for steel flashings and 10mm for aluminium. 8.5.4 Parapet Cappings shows an example of a parapet cap expansion detail.

8.5.3B Stepped fascia corrugate under barge. 8.5.3C Stepped fascia corrugate over barge.

10.10.1.2 Vents above fascia may require re-positioning of the fascia to allow for their depth. Fascia vents should be used in conjunction with a high fronted spouting so that the ends of the sheet and the vent are not exposed to driven rain.

Supporting documentation

The following additional documentation supports the above statements.

DOCUMENT NAME	WEBLINKS
140mm N-Line Fascia brochure & specification document	140N-Line Fascia Brochure and Specifications 2021.pdf
140mm N-Line construction & drop height details	140 N-Line Fascia Construction and Drop Height Details Metal and Concrete Roofing 2021.pdf
Colorcote BPIR document	Colorcote - MagnaFlow Datasheet 2023-1.pdf (colorcote.co.nz)
Colorsteel BPIR document	NZ Steel Product Information Documents
Maintenance document	Continuous Group Maintenance Document.pdf
Material compatibility selection	Continuous Group Material Compatibility - Material Selection v1.pdf
Material compatibility in contact	Continuous Group Material Compatibility - Compatibility of materials in contact v1.pdf
Material compatibility subject to run off	Continuous Group Material Compatibility - Compatibility of materials subject to run off v1.pdf
Warranty document	Continuous Group Warranties

Manufacturing and supply locations

TABLE 3 — CONTINUOUS GROUP MANUFACTURING AND/OR SUPPLY LOCATIONS

LOCATION	COMPANY DETAILS
Northland	Northland Continuous Spouting Ltd (NZBN 9429032689105) 2 Sammaree Place, Kerikeri — northland@continuous.co.nz
Auckland	Continuous Spouting Auckland Ltd (NZBN 9429034029862) 94 Takanini School Road, Takanini, Auckland — auckland@continuous.co.nz
Waikato	Continuous Waikato and Bay of Plenty Ltd (NZBN 9429030330535) 141 Queens Street, Leamington, Cambridge — waikato@continuous.co.nz
Bay of Plenty	Continuous Waikato and Bay of Plenty Ltd (NZBN 9429030330535) 31B Enterprise Drive, Papamoa, Tauranga — bop@continuous.co.nz
Gisborne	Streetwise Spouting Ltd (NZBN 9429042306276) 4 Leith Street, Gisborne — gisborne@continuous.co.nz
Hawke's Bay	Rooftech Hawke's Bay Ltd (NZBN 9429035443889) 2/7 Cadbury Road, Onekawa, Napier — hawkes_bay@continuous.co.nz
Taranaki	Gutter Solutions Ltd (NZBN 9429036739240) Unit 2, 20 Pacific Place, Gonville, Whanganui — taranaki@continuous.co.nz
Whanganui / Manawatu	Gutter Solutions Ltd (NZBN 9429036739240) Unit 2, 20 Pacific Place, Gonville, Whanganui — manawatu@continuous.co.nz
Wellington	Wellington Continuous Spouting Ltd (NZBN 9429043333974) Unit B, 1 Prosser Street, Porirua — wellington@continuous.co.nz
Nelson / Marlborough	Continuous Spouting South Ltd (NZBN 9429050107209) 7 Fuji Court, Stoke, Nelson — nelson@continuous.co.nz
Westland	Continuous Spouting South Ltd (NZBN 9429050107209) 51-57 Revel Street, Hokitika — westland@continuous.co.nz
Christchurch / North Canterbury	Continuous Spouting South Ltd (NZBN 9429050107209) 16 Westland Place, Izone Industrial Estate, Rolleston — canterbury@continuous.co.nz
Mid / South Canterbury	Continuous Spouting South Ltd (NZBN 9429050107209) 126 Dobson Street, Ashburton — canterbury@continuous.co.nz
Central Otago	Continuous Spouting South Ltd (NZBN 9429050107209) 7 Connelly Way, Cromwell — otago@continuous.co.nz
Coastal Otago	Continuous Spouting South Ltd (NZBN 9429050107209) 8 Benson Close, Mosgiel — otago@continuous.co.nz
Southland	Continuous Spouting South Ltd (NZBN 9429050107209) 72 Leet Street, Invercargill — southland@continuous.co.nz

Continuous Group are members of the NZ Metal Roofing Manufacturers Incorporated and the Roofing Association of New Zealand.