150MM ROUND · FS-150

150MM DOWNPIPE



FS-150

Our largest round downpipe. FS-150 moves 19,600mm² of water for commercial and industrial catchments — clamp fixed at up to 1800mm centres, in a pre-painted steel finish.

Ideally suited for commercial and industrial roofs with very large catchments.

- 150mm round roll-formed downpipe
- 19,600mm² cross-section capacity
- Diecast clamp bracket, 40–140mm off-set
- Brackets at up to 1800mm centres
- Colour matched to your spouting
- 15 year perforation warranty

SPECIFY YOUR 150MM DOWNPIPE

FINISH RANGE	DOWNPIPE MATERIAL	COLOUR CHOICE	BRACKETS
CG Range	ColorCote MagnaFlow pre-painted G300 steel, min 150gsm	17 CG Colours	Clamp
Designer Range	ColorCote MagnaFlow pre-painted G300 steel, min 150gsm or ColorSteel Maxam, min 150gsm	25 Designer Colours	Clamp
Specialty Range	ColorCote MagnaFlow pre-painted G300 steel, min 150gsm or ColorSteel Maxam, min 150gsm	20 Specialty Colours	Clamp

AVAILABLE FITTINGS
95° and 30° bends, joiners

CAPACITY
19,600mm² cross-section

For downpipe calculations by roof area, refer to MRM Code of Practice sections 5.4.1, 5.4.2 and 5.7.



150mm Downpipe



150mm Adjustable clamp



150mm 95° bend



150mm 30° bend

Additional components available.

0800 50 1993
www.continuous.co.nz
cg@continuous.co.nz


All information, images and drawings are correct at time of publication August 2026

TECHNICAL SPECIFICATION

FS-150 150mm Round Downpipe

CONTINUOUS GROUP Made first. Made to last.

CROSS-SECTION



Ø inside	**158mm**
Ø outside	**159.2mm**
Capacity	**19,600mm²**

DIMENSIONS & CAPACITY

Model	**FS-150**
Series	**Form Series**
Profile	**150mm round**
Inside diameter	**158mm**
Outside diameter	**159.2mm**
Cross-section capacity	**19,600mm²**
Finish ranges	**CG, Designer, Specialty**

All dimensions ±1mm; capacity is cross-sectional area.

PRODUCT SPECIFICATIONS

Downpipe material	**MAG-150**	MagnaFlow pre-painted G300 steel, min 150gsm alloy/zinc/magnesium
	MAXAM-150	ColorSteel Maxam pre-painted G300 steel, min 150gsm alloy/zinc/magnesium
Brackets	**Clamp**	Diecast aluminium — 40–140mm wall off-set
Bracket spacing	**Maximum**	1800mm centreline
	First bracket	Within 300mm of the dropper or first bend
Recommended fixings	**Fasteners**	Minimum Class 4 screw and/or rivet, matched to substrate and bracket material. Stainless steel fixings and components are not compatible with our materials
	Soft claddings	Timber fixing points required, e.g. polystyrene with plaster
Available fittings	95° and 30° bends, joiners	

NOT SEALED — IMPORTANT LIMITATION

FS-150 is roll-formed and lock-seamed. It is **not** sealed or designed for head pressure — no tank collection, no runs inside the building envelope, no charged lines, and not where tank head height is above the top of the stormwater drain. Specify **Ezi-Flo Series** with a sealed pressure coupling for charged lines and elevated tanks. All stormwater drains to be per MRM Code of Practice section 5.4 and E1/AS1 section 3.

SCOPE OF USE

Form Series downpipes collect and channel water that runs off a roof, with the downpipes placed at the building perimeter, positioned outside the building envelope.

NZBC COMPLIANCE

Test information available from Pacific Coilcoaters and New Zealand Steel, combined with the past history of rainwater products, indicates that provided product use and maintenance is in line with the guidelines in current literature, Continuous Group rainwater systems can be expected to meet the performance criteria in clause E2 of the New Zealand Building Code.

DURABILITY

Pre-painted steel products are fit for purpose in environment zones B and C;* zone D may require a pre-approval warranty application based on the site address.*

*In all cases, areas with high wind and/or salt and/or thermal or industrial atmospheric conditions may require specific engineering design (SED). Reference: Section 4, "Durability", NZS 3604:2011.

MAINTENANCE

Continuous Group rainwater systems require regular maintenance to ensure the useful life of the products. Minimum maintenance interval of every 6 months, or as often as needed to avoid build-up of contaminants such as dirt, salt and pollen on the downpipe surface. Simply spray and rinse with water and, if necessary, scrub with a soft nylon brush. Specific maintenance products are listed in our Care & Maintenance document.

WARRANTY

MagnaFlow pre-painted steel*
15 year perforation, 10 year paint. Zones B and C; zone D subject to a pre-approval warranty application.

Maxam pre-painted steel*
15 year perforation, 10 year paint. Zones B and C; zone D subject to a pre-approval warranty application.

*Subject to manual washing. High wind, salt, thermal or industrial atmospheres may require specific engineering design (SED); reference Section 4 "Durability", NZS 3604:2011. Full Warranty details and conditions are on our website.

All information, images and drawings are correct at time of publication August 2026